

# LEHIGH

## HEIDELBERGCEMENT Group

TECHNICAL SERVICES SALES & MARKETING

12667 Alcosta Blvd., Suite 400  
San Ramon, CA 94583  
Telephone (925) 244 6500  
FAX (925) 244 6586

PERMANENTE PLANT

24001 Stevens Creek Blvd.  
Cupertino, CA 95014-5659  
Telephone (408) 996-4033  
FAX (408) 996-4033

### CEMENT TEST REPORT

**Cement:** Permanente Type II-V, Low Alkali; ASTM C 150-09

STANDARD CHEMICAL REQUIREMENTS ASTM C 114	TEST RESULTS	ASTM C 150 SPECIFICATIONS	
		TYPE II	TYPE V
Silicon Dioxide (SiO <sub>2</sub> ), %	21.9	20.0 Min	----
Aluminum Oxide (Al <sub>2</sub> O <sub>3</sub> ), %	3.8	6.0 Max	----
Ferric Oxide (Fe <sub>2</sub> O <sub>3</sub> ), %	3.8	6.0 Max	----
Calcium Oxide (CaO), %	65.7	----	----
Magnesium Oxide (MgO), %	0.7	6.0 Max	6.0 Max
Sulfur Trioxide (SO <sub>3</sub> ), %	2.7	3.0 Max	2.3 <sup>B</sup> Max
Loss on Ignition (LOI), %	0.5	3.0 Max	3.0 Max
Insoluble Residue, %	0.18	0.75 Max	0.75 Max
Alkalies (Na <sub>2</sub> O equivalent), %	0.21	0.60 Max	0.60 Max
Tricalcium Silicate (C <sub>3</sub> S), %	63	----	----
Dicalcium Silicate (C <sub>2</sub> S), %	15	----	----
Tricalcium Aluminate (C <sub>3</sub> A), %	4	8 Max	5 Max
Tetracalcium Aluminoferrite (C <sub>4</sub> AF), %	11	----	----
2 (C <sub>3</sub> A) + C <sub>4</sub> AF, %	19	----	25 Max
PHYSICAL REQUIREMENTS			
(ASTM C 1038) Expansion @ 14 days, % (previous month)	0.006	0.020 Max	0.020 Max
(ASTM C 452) Expansion @ 14 days, % (previous month)	0.020	----	0.04 Max
(ASTM C 430) -325 Mesh, %	99.6	----	----
(ASTM C 204) Blaine, m <sup>2</sup> /kg	331	280 Min	280 Min
(ASTM C114) Limestone, max, %	2.5	5 Max	5 Max
(ASTM C114) Limestone, %CaCO <sub>3</sub>	94.6	----	----
(ASTM C114) Cement, %CO <sub>2</sub>	1.04	----	----
(ASTM C 191) Time of Setting - Initial (Vicat)	129	45 Min	45 Min
(ASTM C 191) Time of Setting - Final (Vicat)	264	375 Max	375 Max
(ASTM C 451) False Set, %	93	50 Min	50 Min
(ASTM C 185) Air Content, %	6.4	12 Max	12 Max
(ASTM C 151) Autoclave Expansion, %	0.01	0.80 Max	0.80 Max
(ASTM C 187) Normal Consistency, %	24.8	----	----
(ASTM C 109) Compressive Strength, psi (MPa)			
1 Day	1718	----	----
3 Day	3356	1500 (10.3) Min	1160 (8.0) Min
7 Day	4847	2500 (17.2) Min	2180 (15.0) Min
28 Day (previous month)	7847	----	3050 (21.0) Min

This cement meets the requirements of specification:

ASTM C150-09 Type II-V, Low Alkali

Caltrans Section 90-2.01 - Type II-V Modified



Alan Sabawi, Quality Control Manager

**Applicable ASTM C 150 Notes:**

**Note B:** There are cases where the optimum SO<sub>3</sub> (using Test Method C563) for a particular cement is close to or in excess of the limit in this specification. In such cases where properties of a cement can be improved by exceeding the SO<sub>3</sub> limit stated in this table it is permissible to exceed the values in the table, provided it has been demonstrated by Test Method C1038 that the cement with the increased SO<sub>3</sub> will not develop expansion in water exceeding 0.020% at 14 days. When the manufacturer supplies cement under this provision, he shall, upon request, supply supporting data to the purchaser.

**Note C:** Limestone addition as per C 150-05 Item 5.1.3